

Project First Light  
Destination Resort Casino  
Taunton, Massachusetts  
*EEA# 14924*

**Submitted to:**

MEPA Office  
Executive Office of Energy  
and Environmental Affairs  
100 Cambridge Street, Suite 900  
Boston, MA 02114

**Submitted by:**

Mashpee Wampanoag Tribe  
483 Great Neck Road South  
Mashpee, MA 02649

**Prepared by:**

Epsilon Associates, Inc.  
3 Clock Tower Place, Suite 250  
Maynard, MA 01754

**In Association with:**

JCJ Architecture  
Howard/Stein-Hudson Associates, Inc.  
Fay, Spofford & Thorndike, Inc.  
Field Engineering Co., Inc.  
GEI Consultants, Inc.  
AKRF, Inc.

December 1, 2014

## Table of Contents

---

---

# Table of Contents

---

<b>1.0</b>	<b>PROJECT OVERVIEW AND DESCRIPTION</b>	<b>1-1</b>
1.1	Introduction	1-1
1.2	Purpose and Need	1-1
1.3	Project Site	1-2
1.4	Changes to the Project since Publication of the DEIR	1-4
1.5	Summary of Alternatives	1-5
1.5.1	Alternative A: Preferred Alternative	1-5
1.5.2	Alternative B: Reduced Intensity I	1-5
1.5.3	Alternative C: Reduced Intensity II	1-6
1.5.4	Alternative D: No Action	1-6
1.6	Current Environmental Review Status	1-7
1.6.1	MEPA	1-7
1.6.2	Fee to Trust Status	1-7
1.6.3	National Environmental Policy Act	1-9
1.7	Public Involvement and Agreements	1-10
1.7.1	Intergovernmental Agreement	1-10
1.7.2	City Referendum	1-11
1.7.3	Tribal-State Compact	1-11
1.7.4	Tribal Outreach and Coordination	1-12
1.8	Statutory and Regulatory Standards and Requirements	1-13
1.8.1	State and Local Compliance	1-13
1.8.2	Required Permits, Approvals, and Regulatory Compliance	1-16
1.8.2.1	Federal Permits	1-16
1.8.2.2	Required Permits	1-18
1.9	Construction Schedule	1-18
1.10	Cost	1-18
1.11	Summary of Environmental Impacts	1-19
<b>2.0</b>	<b>ALTERNATIVES</b>	<b>2-1</b>
2.1	Introduction	2-1
2.2	Description of Project Alternatives	2-1
2.2.1	Alternative A: Preferred Alternative	2-1
2.2.2	Alternative B: Reduced Intensity I	2-2
2.2.3	Alternative C: Reduced Intensity II	2-2
2.2.4	Summary of Development Alternatives	2-3

## Table of Contents (Continued)

---

2.2.5	Alternative D: No Action	2-4
<b>3.0</b>	<b>TRANSPORTATION</b>	<b>3-1</b>
3.1	Overview	3-1
3.1.1	Project Description	3-1
3.1.2	Site Access	3-3
3.1.3	Study Area	3-3
3.1.3.1	Signalized Intersections	3-3
3.1.3.2	Unsignalized Intersections	3-7
3.1.3.3	Route 24 and 140 Interchange.	3-9
3.1.3.4	Freeway Segment Operations	3-9
3.2	Existing Transportation Conditions	3-9
3.2.1	Roadway Conditions	3-9
3.2.2	Intersection Conditions	3-12
3.2.2.1	Signalized Intersections	3-12
3.2.2.2	Unsignalized Intersections	3-19
3.2.3	Interchange Conditions	3-27
3.2.4	Data Collection Program	3-29
3.2.5	Roadway Volumes	3-30
3.2.6	Intersection Volumes	3-31
3.2.7	Interchange Volumes	3-31
3.2.8	Peak Hours	3-31
3.2.9	Seasonal Adjustment Factors	3-49
3.2.10	Consistency with MassDOT Recorded Volumes	3-49
3.2.11	Safety Analysis	3-50
3.2.11.1	Intersection Safety Analysis	3-50
3.2.11.2	Routes 24 and 140 Freeway Segments: Detailed Crash Analysis	3-52
3.2.12	Operations Analysis	3-54
3.2.12.1	Definitions and Methodology	3-54
3.2.12.2	AM Peak Hour Intersection Operations	3-62
3.2.12.3	Friday PM Peak Hour Intersection Operations	3-63
3.2.12.4	Saturday Midday Peak Hour Intersection Operations	3-67
3.2.12.5	Interchange Operations	3-68
3.2.13	Existing Transit and Ridesharing Service	3-73
3.2.13.1	GATRA Bus Service	3-73
3.2.13.2	MBTA Commuter Rail Service	3-76
3.2.13.3	Brockton Area Transit Authority Service	3-78
3.2.13.4	Southeastern Regional Transit Authority Service	3-78
3.2.13.5	Private Bus Service	3-78
3.2.13.6	Vanpools/Carpools	3-80

## Table of Contents (Continued)

---

	3.2.13.7	Park-and-Ride	3-80
	3.2.13.8	MassDOT Rail Right-of-Way	3-81
	3.2.14	Existing Pedestrian and Bicycle Conditions	3-81
	3.2.15	Aviation	3-81
3.3		Evaluation of Long-Term Impacts (2022)	3-82
	3.3.1	No-Build (2022) Conditions	3-82
	3.3.1.1	Background Traffic Volumes	3-82
	3.3.1.2	Proposed Roadway and Transit Improvements	3-83
	3.3.1.3	LUIP Phase 1 and 2 Buildout Traffic	3-91
	3.3.1.4	No-Build (2022) Intersection Operations Analysis	3-94
	3.3.1.5	No-Build (2022) Interchange Operations Analysis	3-111
	3.3.2	Impact Analysis: Build Alternatives	3-119
	3.3.2.1	Vehicle Trip Generation	3-122
	3.3.2.2	Trip Distribution	3-129
	3.3.2.3	Build (2022) Conditions Operations Analysis: Alternative A (Preferred Alternative)	3-130
	3.3.2.4	Proposed Mitigating Measures: Alternative A	3-185
	3.3.2.5	Build (2022) Conditions Operations Analysis: Alternative B	3-209
	3.3.2.6	Proposed Mitigating Measures: Alternative B	3-217
	3.3.2.7	Build (2022) Conditions Operations Analysis: Alternative C	3-218
	3.3.2.8	Impact Analysis: Parking	3-218
	3.3.2.9	Impact Analysis: Public Transportation	3-221
	3.3.2.10	Impact Analysis: Pedestrians and Bicycles	3-226
	3.3.2.11	Impact Analysis: Aviation	3-226
	3.3.2.12	Transportation Demand Management Measures	3-226
3.4		Evaluation of 2032 Conditions	3-228
	3.4.1	Operations Analysis for 20-Year Horizon (2032)	3-228
	3.4.1.1	No-Build (2032) Operations Analysis: Route 140 Interchanges	3-228
	3.4.1.2	Build Alternative A (2032) Operations Analysis: Route 140 Interchanges	3-229
	3.4.2	MassDOT Option 1D (2032)	3-234
	3.4.2.1	No-Build (2032) Operations Analysis: Route 140 Interchanges with MassDOT Option 1D	3-234
	3.4.2.2	Build Alternative A (2032) Operations Analysis: Route 140 Interchanges with MassDOT Option 1D	3-237
3.5		Conclusions	3-240

## Table of Contents (Continued)

---

<b>4.0</b>	<b>AIR QUALITY</b>	<b>4-1</b>
4.1	Introduction	4-1
4.2	Existing Air Quality	4-1
	4.2.1 National Ambient Air Quality Standards	4-1
	4.2.2 Ambient Concentrations	4-2
4.3	Methodology	4-4
4.4	Air Quality Results	4-4
4.5	Conclusions	4-7
<b>5.0</b>	<b>GREENHOUSE GAS EMISSIONS ANALYSIS</b>	<b>5-1</b>
5.1	Introduction and Project Overview	5-1
	5.1.1 MEPA Greenhouse Gas Emissions Policy and Protocol	5-1
	5.1.2 Project Overview	5-3
	5.1.3 Outline of the Remainder of this Section	5-3
5.2	Quantification: Direct & Indirect Emissions	5-4
	5.2.1 Modeling Method	5-4
	5.2.2 Description of HVAC System	5-5
	5.2.3 Listing of Modeling Inputs	5-6
5.3	Quantification: Transportation Emissions	5-6
5.4	Quantification: Water & Wastewater Emissions	5-7
5.5	Quantification: Water Park Emissions	5-7
5.6	Quantification: Summary & Comparison	5-9
	5.6.1 Quantification Summary	5-9
	5.6.2 Comparison: Reduced Intensity Alternatives	5-11
	5.6.3 Comparison: Water-Source Heat Pump Option	5-11
	5.6.4 Comparison: Energy Use Index	5-11
5.7	Potential Mitigation Measures: Energy Use Reduction	5-12
	5.7.1 Siting, Site Design, and Development	5-12
	5.7.2 Building Envelope	5-14
	5.7.3 Building Mechanical Systems and Lighting	5-16
	5.7.4 Water Conservation	5-19
	5.7.5 Materials	5-20
	5.7.6 Energy Information (Data Acquisition)	5-20
	5.7.7 Ongoing Operations	5-21
5.8	Potential Mitigation Measures: Energy Generation	5-22
	5.8.1 Combined Heat and Power	5-22
	5.8.2 Ground Source Heat Pumps	5-24
	5.8.3 Wind Turbines	5-24
	5.8.4 Solar Hot Water	5-26
	5.8.5 Solar Photovoltaic	5-31

## Table of Contents (Continued)

---

5.8.6	Anaerobic Digestion & Organics Diversion	5-39
5.9	GHG Reduction Funding Alternatives	5-39
5.9.1	Federal Tax Credits	5-39
5.9.2	Massachusetts Clean Energy Center	5-40
5.9.3	Taunton Municipal Light Plant	5-41
5.9.4	Renewable Energy Credits	5-43
5.9.5	Tribal Funding Opportunities	5-43
5.10	Commitment to Mitigation Measures	5-44
<b>6.0</b>	<b>WATER SUPPLY</b>	<b>6-1</b>
6.1	Existing Conditions	6-1
6.1.1	City of Taunton Water Supply	6-1
6.1.2	Water Supply System Serving Project Site	6-4
6.1.3	Existing Demand at Project Site	6-4
6.2	Environmental Consequences	6-5
6.2.1	Introduction	6-5
6.2.2	Alternative A: Preferred Alternative	6-6
6.2.3	Alternative B: Reduced Intensity I	6-8
6.2.4	Alternative C: Reduced Intensity II	6-8
6.2.5	Alternative D: No Action	6-9
6.3	Mitigation	6-9
6.3.1	Alternatives A, B, and C	6-9
6.3.2	Alternative D	6-11
<b>7.0</b>	<b>WASTEWATER</b>	<b>7-1</b>
7.1	Existing Conditions	7-1
7.1.1	City of Taunton Wastewater Treatment	7-1
7.1.2	Wastewater Collection System Servicing Project Site	7-1
7.1.3	Existing Flow at Project Site	7-2
7.2	Environmental Consequences	7-2
7.2.1	Introduction	7-2
7.2.2	Alternative A: Preferred Alternative	7-3
7.2.2.1	Impacts to Wastewater Collection System	7-3
7.2.2.2	Impacts of Wastewater Treatment System	7-5
7.2.2.3	Mitigation	7-6
7.2.3	Alternative B: Reduced Intensity I	7-6
7.2.3.1	Impacts to Wastewater Collection System	7-6
7.2.3.2	Impacts of Wastewater Treatment System	7-6
7.2.3.3	Mitigation	7-7
7.2.4	Alternative C: Reduced Intensity II	7-7
7.2.4.1	Impacts to Wastewater Collection System	7-7

## Table of Contents (Continued)

---

	7.2.4.2	Impacts of Wastewater Treatment System	7-7
	7.2.4.3	Mitigation	7-7
	7.2.5	Alternative D: No Action	7-7
	7.2.5.1	Impacts to Wastewater Collection System	7-7
	7.2.5.2	Impacts of Wastewater Treatment System	7-8
	7.2.5.3	Mitigation	7-8
<b>8.0</b>	<b>LAND</b>		<b>8-1</b>
8.1	Existing Conditions		8-1
8.2	Environmental Consequences		8-1
	8.2.1	Ground Cover	8-1
		8.2.1.1 Preferred Alternative	8-1
		8.2.1.2 Alternative B: Reduced Intensity I	8-2
		8.2.1.3 Alternative C: Reduced Intensity II	8-3
		8.2.1.4 No Action	8-3
	8.2.2	Parking Alternatives	8-9
<b>9.0</b>	<b>WETLANDS</b>		<b>9-1</b>
9.1	Review of Wetland Impact Avoidance and Minimization Measures since Publication of the Draft EIR		9-1
9.2	Update on Wetland Resource Area Boundaries		9-2
9.3	Barstows Pond Dam Removal Project		9-8
9.4	Taunton River		9-9
9.5	Summary of Alterations to On-Site Wetland Resource Areas related to Gaming Trust Activities		9-10
	9.5.1	Alternative A: Preferred Alternative Wetland Resource Area Impact Avoidance and Minimization Measures	9-10 9-15
	9.5.2	Review of Other Project Site Development Alternatives	9-16
		9.5.2.1 Alternative B: Reduced Intensity I	9-16
		9.5.2.2 Alternative C: Reduced Intensity II	9-17
		9.5.2.3 Alternative D: No Action	9-17
9.6	Summary of Alterations to Off-Site Wetland Resource Areas for Transportation Improvement Mitigation		9-24
	9.6.1	Alternative A: Preferred Alternative Wetland Resource Area Impact Avoidance and Minimization Measures	9-24 9-38
	9.6.2	Alternative B: Reduced Intensity I	9-39
	9.6.3	Alternative C: Reduced Intensity II	9-39
	9.6.4	Alternative D: No Action	9-39



## Table of Contents (Continued)

---

9.7	Mitigation Measures	9-40
9.8	Information Demonstrating Compliance with Wetlands Protection Act Regulations and Performance Standards for the Preferred Alternative	9-43
9.8.1	Riverfront Area	9-44
9.8.2	Bordering Land Subject to Flooding	9-50
9.8.3	Other Resource Areas	9-52
9.9	Limited Project Criteria for Proposed Route 24/140 Intersection Improvements	9-52
9.10	Compliance with State 401 Water Quality Certification Criteria	9-54
<b>10.0</b>	<b>STORMWATER</b>	<b>10-1</b>
10.1	Existing Conditions	10-1
10.2	Environmental Consequences	10-4
10.2.1	Introduction	10-4
10.2.2	Stormwater Management System	10-5
10.2.2.1	Alternative A: Preferred Alternative	10-5
10.2.2.2	Alternative B: Reduced Intensity I	10-16
10.2.2.3	Alternative C: Reduced Intensity II	10-16
10.2.2.4	Alternative D: No Action	10-17
10.2.3	Construction Period Stormwater Management	10-17
10.2.4	Conclusion	10-18
<b>11.0</b>	<b>HAZARDOUS MATERIALS</b>	<b>11-1</b>
11.1	Existing Conditions	11-1
11.1.1	Phase I Site Assessment	11-1
11.1.2	Hazardous Materials on Rail Line	11-3
11.2	Environmental Consequences	11-3
11.2.1	Alternative A: Preferred Alternative	11-3
11.2.2	Alternative B: Reduced Intensity I	11-3
11.2.3	Alternative C: Reduced Intensity II	11-4
11.2.4	Alternative D: No Action	11-4
11.3	Mitigation	11-4
11.3.1	Alternatives A, B, and C	11-4
11.3.2	Alternative D	11-5
<b>12.0</b>	<b>HISTORIC AND ARCHAEOLOGICAL RESOURCES</b>	<b>12-1</b>
12.1	Introduction	12-1
12.2	Historic Properties	12-1
12.3	Archaeological Resources	12-1
12.4	Potential Effects and Consultation	12-2

## Table of Contents (Continued)

---

<b>13.0</b>	<b>CONSTRUCTION PERIOD</b>	<b>13-1</b>
13.1	Construction Schedule and Approach	13-1
13.1.1	Alternative A: Preferred Alternative	13-1
13.1.2	Alternative B: Reduced Intensity I	13-2
13.1.3	Alternative C: Reduced Intensity II	13-2
13.1.4	Alternative D: No Action	13-2
13.2	Construction Methodology	13-3
13.2.1	Alternative A: Preferred Alternative	13-3
13.2.1.1	On-Site Work	13-3
13.2.1.2	Off-Site Traffic Improvements	13-4
13.2.1.3	Water Main and Sewer Extension	13-5
13.2.2	Alternative B: Reduced Intensity I	13-6
13.2.2.1	On-Site Work	13-6
13.2.2.2	Off-Site Traffic Improvements	13-7
13.2.2.3	Water Main and Sewer Extension	13-7
13.2.3	Alternative C: Reduced Intensity II	13-7
13.2.3.1	On-Site Work	13-7
13.2.3.2	Off-Site Traffic Improvements	13-8
13.2.3.3	Water Main and Sewer Extension	13-8
13.2.4	Alternative D: No Action	13-8
13.2.4.1	On-Site Work	13-8
13.2.4.2	Off-Site Traffic Improvements	13-9
13.2.4.3	Water Main and Sewer Extension	13-9
13.3	Potential Impacts and Mitigation	13-9
13.3.1	Alternative A: Preferred Alternative	13-9
13.3.1.1	Construction Noise	13-9
13.3.1.2	Blasting and Vibration	13-10
13.3.1.3	Groundwater Level Monitoring During Construction	13-10
13.3.1.4	Air Quality	13-11
13.3.1.5	Construction and Demolition Waste	13-11
13.3.1.6	Construction Period Stormwater Management and Erosion/Sedimentation Control	13-12
13.3.1.7	Site Preparation, Construction Staging and General Construction Requirements	13-13
13.3.1.8	Construction Traffic	13-13
13.3.1.9	Aviation Safety	13-17
13.3.1.10	Construction Work Hours	13-17
13.3.1.11	Rodent Control	13-17

## Table of Contents (Continued)

---

13.3.2	Alternative B: Reduced Intensity I	13-18
13.3.2.1	Construction Noise	13-18
13.3.2.2	Blasting and Vibration	13-18
13.3.2.3	Groundwater Level Monitoring During Construction	13-18
13.3.2.4	Air Quality	13-18
13.3.2.5	Construction and Demolition Waste	13-18
13.3.2.6	Construction Period Stormwater Management and Erosion/Sedimentation Control	13-18
13.3.2.7	Site Preparation, Construction Staging and General Construction Requirements	13-19
13.3.2.8	Construction Traffic	13-19
13.3.2.9	Aviation Safety	13-19
13.3.2.10	Construction Work Hours	13-20
13.3.2.11	Rodent Control	13-20
13.3.3	Alternative C: Reduced Intensity II	13-20
13.3.3.1	Construction Noise	13-20
13.3.3.2	Blasting and Vibration	13-20
13.3.3.3	Groundwater Level Monitoring During Construction	13-20
13.3.3.4	Air Quality	13-20
13.3.3.5	Construction and Demolition Waste	13-20
13.3.3.6	Construction Period Stormwater Management and Erosion/Sedimentation Control	13-21
13.3.3.7	Site Preparation, Construction Staging and General Construction Requirements	13-21
13.3.3.8	Construction Traffic	13-21
13.3.3.9	Aviation Safety	13-22
13.3.3.10	Construction Work Hours	13-22
13.3.3.11	Rodent Control	13-22
13.3.4	Alternative D: No Action	13-22
13.3.4.1	Construction Noise	13-22
13.3.4.2	Blasting and Vibration	13-22
13.3.4.3	Groundwater Level Monitoring During Construction	13-22
13.3.4.4	Air Quality	13-22
13.3.4.5	Construction and Demolition Waste	13-23
13.3.4.6	Construction Period Stormwater Management and Erosion/Sedimentation Control	13-23
13.3.4.7	Site Preparation, Construction Staging and General Construction Requirements	13-23
13.3.4.8	Construction Traffic	13-23
13.3.4.9	Aviation Safety	13-24

## Table of Contents (Continued)

---

	13.3.4.10 Construction Work Hours	13-24
	13.3.4.11 Rodent Control	13-24
<b>14.0</b>	<b>MITIGATION AND PROPOSED SECTION 61 FINDINGS</b>	<b>14-1</b>
14.1	Mitigation Measures	14-1
14.1.1	Transportation	14-1
14.1.1.1	Construction Period	14-1
14.1.1.2	Operational Impacts	14-1
14.1.1.3	Public Transportation	14-3
14.1.1.4	Pedestrian and Bicycles	14-4
14.1.1.5	Transportation Demand Management Measures	14-4
14.1.2	Air Quality	14-5
14.1.2.1	Construction Period	14-5
14.1.2.2	Operational Impacts	14-6
14.1.3	Greenhouse Gas Impacts	14-6
14.1.4	Water Supply	14-7
14.1.5	Wastewater	14-8
14.1.6	Land Impacts	14-9
14.1.7	Wetlands	14-9
14.1.7.1	Construction Period	14-9
14.1.7.2	Bordering Vegetated Wetlands	14-10
14.1.7.3	Bordering Land Subject to Flooding	14-11
14.1.8	Stormwater	14-12
14.1.8.1	Construction Period	14-12
14.1.8.2	Operational Impacts	14-12
14.1.8.3	Off-Site Impacts	14-13
14.1.9	Hazardous Materials	14-13
14.1.10	Historic Resources	14-14
14.2	Proposed Section 61 Findings	14-14
14.2.1	Department of Transportation Proposed Section 61 Findings	14-16
14.2.2	Department of Environmental Protection Proposed Section 61 Findings	14-21
<b>15.0</b>	<b>RESPONSES TO COMMENTS</b>	<b>15-1</b>
<b>16.0</b>	<b>CIRCULATION LIST</b>	<b>16-1</b>

## List of Appendices

---

Appendix A	Transportation
Appendix B	Air Quality
Appendix C	Greenhouse Gas Analysis
Appendix D	Water Supply
Appendix E	Wetlands
Appendix F	Stormwater Report
Appendix G	Construction Management Plan

## List of Figures

---

Figure 1.3-1	Project Site Parcels	1-3
Figure 2.2-1	Alternative A: Preferred Alternative	2-6
Figure 2.2-2	Alternative B: Reduced Intensity I	2-7
Figure 2.2-3	Alternative C: Reduced Intensity II	2-8
Figure 2.2-4	Alternative D: No Action	2-9
Figure 3.1-1	Locus Map	3-2
Figure 3.1-2	Existing Site Access	3-4
Figure 3.1-3	Study Area Intersections – Taunton	3-5
Figure 3.1-4	Study Area Intersections – Expanded Area	3-6
Figure 3.2-1	Daily Traffic Variations – Route 24 north of Route 140	3-32
Figure 3.2-2	Daily Traffic Variations – Route 140 east of Route 24	3-33
Figure 3.2-3	Existing Conditions (2012) AM Peak Hour Volumes – West Taunton	3-34
Figure 3.2-4	Existing Conditions (2012) AM Peak Hour Volumes – East Taunton	3-35
Figure 3.2-5	Existing Conditions (2012) AM Peak Hour Volumes – Route 44 Corridor	3-36
Figure 3.2-6	Existing Conditions (2012) AM Peak Hour Volumes – Other Local Intersections	3-37
Figure 3.2-7	Existing Conditions (2012) PM Peak Hour Volumes – West Taunton	3-38
Figure 3.2-8	Existing Conditions (2012) PM Peak Hour Volumes – East Taunton	3-39
Figure 3.2-9	Existing Conditions (2012) PM Peak Hour Volumes – Route 44 Corridor	3-40
Figure 3.2-10	Existing Conditions (2012) PM Peak Hour Volumes – Other Local Intersections	3-41
Figure 3.2-11	Existing Conditions (2012) Saturday Midday Peak Hour Volumes – West Taunton	3-42
Figure 3.2-12	Existing Conditions (2012) Saturday Midday Peak Hour Volumes – East Taunton	3-43
Figure 3.2-13	Existing Conditions (2012) Saturday Midday Peak Hour Volumes – Route 44 Corridor	3-44
Figure 3.2-14	Existing Conditions (2012) Saturday Midday Peak Hour Volumes – Other Local Intersections	3-45

## List of Figures (Continued)

---

Figure 3.2-15	Existing Conditions (2012) Interchange Volumes – Route 140 Interchanges	3-46
Figure 3.2-16	Existing Conditions (2012) Interchange Volumes – Route 24 Interchanges	3-47
Figure 3.2-17	Existing Conditions (2012) Interchange Volumes – Other Area Interchanges	3-48
Figure 3.2-18	Detailed Crash Analysis – Route 24 and Route 140 Freeway Segments	3-53
Figure 3.2-19	Existing Conditions (2012) Intersection LOS Summary – West Taunton	3-58
Figure 3.2-20	Existing Conditions (2012) Intersection LOS Summary – East Taunton	3-59
Figure 3.2-21	Existing Conditions (2012) Intersection LOS Summary – Route 44 Corridor	3-60
Figure 3.2-22	Existing Conditions (2012) Intersection LOS Summary – Other Local Intersections	3-61
Figure 3.2-23	Existing Conditions (2012) Interchange LOS Summary – Route 140 Interchanges	3-70
Figure 3.2-24	Existing Conditions (2012) Interchange LOS Summary – Route 24 Interchanges	3-71
Figure 3.2-25	Existing Conditions (2012) Interchange LOS Summary – Other Area Interchanges	3-72
Figure 3.2-26	Existing Transit Service	3-77
Figure 3.3-1	Proposed Taunton Station Locations – South Coast Rail, Stoughton Alternative	3-84
Figure 3.3-2	MassDOT Approved 25% Design: Harts Four Corners	3-88
Figure 3.3-3	MassDOT Preliminary Alternative: Route 24/140 Interchange Improvements	3-90
Figure 3.3-4	No-Build (2022) AM Peak Hour Volumes – West Taunton	3-95
Figure 3.3-5	No-Build (2022) AM Peak Hour Volumes – East Taunton	3-96
Figure 3.3-6	No-Build (2022) AM Peak Hour Volumes – Route 44 Corridor	3-97
Figure 3.3-7	No-Build (2022) AM Peak Hour Volumes – Other Local Intersections	3-98
Figure 3.3-8	No-Build (2022) PM Peak Hour Volumes – West Taunton	3-99
Figure 3.3-9	No-Build (2022) PM Peak Hour Volumes – East Taunton	3-100
Figure 3.3-10	No-Build (2022) PM Peak Hour Volumes – Route 44 Corridor	3-101
Figure 3.3-11	No-Build (2022) PM Peak Hour Volumes – Other Local Intersections	3-102
Figure 3.3-12	No-Build (2022) Saturday Midday Peak Hour Volumes – West Taunton	3-103
Figure 3.3-13	No-Build (2022) Saturday Midday Peak Hour Volumes – East Taunton	3-104
Figure 3.3-14	No-Build (2022) Saturday Midday Peak Hour Volumes – Route 44 Corridor	3-105
Figure 3.3-15	No-Build (2022) Saturday Midday Peak Hour Volumes – Other Local Intersections	3-106
Figure 3.3-16	No-Build (2022) Intersection LOS Summary – West Taunton	3-107
Figure 3.3-17	No-Build (2022) Intersection LOS Summary – East Taunton	3-108
Figure 3.3-18	No-Build (2022) Intersection LOS Summary – Route 44 Corridor	3-109
Figure 3.3-19	No-Build (2022) Intersection LOS Summary – Other Local Intersections	3-110
Figure 3.3-20	No-Build (2022) Interchange Volumes – Route 140 Interchanges	3-112
Figure 3.3-21	No-Build (2022) Interchange Volumes – Route 24 Interchanges	3-113
Figure 3.3-22	No-Build (2022) Interchange Volumes – Other Area Interchanges	3-114
Figure 3.3-23	No-Build (2022) Interchange LOS Summary – Route 140 Interchanges	3-115
Figure 3.3-24	No-Build (2022) Interchange LOS Summary – Route 24 Interchanges	3-116

## List of Figures (Continued)

---

Figure 3.3-25	No-Build (2022) Interchange LOS Summary – Other Area Interchanges	3-117
Figure 3.3-26	Proposed Site Plan – Build Alternative A	3-120
Figure 3.3-27	Proposed Site Plan – Build Alternative B	3-121
Figure 3.3-28	Proposed Site Plan – Build Alternative C	3-123
Figure 3.3-29	Overall Regional Trip Distribution	3-132
Figure 3.3-30	Regional Trip Distribution – Patrons	3-133
Figure 3.3-31	Regional Trip Distribution - Employees	3-134
Figure 3.3-32	Local Trip Distribution (in Percentages): Patrons – West Taunton	3-135
Figure 3.3-33	Local Trip Distribution (in Percentages): Patrons – East Taunton	3-136
Figure 3.3-34	Local Trip Distribution (in Percentages): Patrons – Route 44 Corridor	3-137
Figure 3.3-35	Local Trip Distribution (in Percentages): Patrons – Other Local Intersections	3-138
Figure 3.3-36	Local Trip Distribution (in Percentages): Employees – West Taunton	3-139
Figure 3.3-37	Local Trip Distribution (in Percentages): Employees – East Taunton	3-140
Figure 3.3-38	Local Trip Distribution (in Percentages): Employees – Route 44 Corridor	3-141
Figure 3.3-39	Local Trip Distribution (in Percentages): Employees – Other Local Intersections	3-142
Figure 3.3-40	Site Circulation: Build Alternative A	3-143
Figure 3.3-41	Project Generate Trips AM Peak Hour Volumes – West Taunton	3-145
Figure 3.3-42	Project Generate Trips AM Peak Hour Volumes – East Taunton	3-146
Figure 3.3-43	Project Generate Trips AM Peak Hour Volumes – Route 44 Corridor	3-147
Figure 3.3-44	Project Generate Trips AM Peak Hour Volumes – Other Local Intersections	3-148
Figure 3.3-45	Project Generate Trips PM Peak Hour Volumes – West Taunton	3-149
Figure 3.3-46	Project Generate Trips PM Peak Hour Volumes – East Taunton	3-150
Figure 3.3-47	Project Generate Trips PM Peak Hour Volumes – Route 44 Corridor	3-151
Figure 3.3-48	Project Generate Trips PM Peak Hour Volumes – Other Local Intersections	3-152
Figure 3.3-49	Project Generate Trips Saturday Midday Peak Hour Volumes – West Taunton	3-153
Figure 3.3-50	Project Generate Trips Saturday Midday Peak Hour Volumes – East Taunton	3-154
Figure 3.3-51	Project Generate Trips Saturday Midday Peak Hour Volumes – Route 44 Corridor	3-155
Figure 3.3-52	Project Generate Trips Saturday Midday Peak Hour Volumes – Other Local Intersections	3-156
Figure 3.3-53	Project Generate Trips Interchange Volume Data – Route 140 Interchanges	3-157
Figure 3.3-54	Project Generate Trips Interchange Volume Data – Route 24 Interchanges	3-158
Figure 3.3-55	Project Generate Trips Interchange Volume Data – Other Area Interchanges	3-159
Figure 3.3-56	Build Alternative A (2022) AM Peak Hour Volumes – West Taunton	3-160
Figure 3.3-57	Build Alternative A (2022) AM Peak Hour Volumes – East Taunton	3-161
Figure 3.3-58	Build Alternative A (2022) AM Peak Hour Volumes – Route 44 Corridor	3-162
Figure 3.3-59	Build Alternative A (2022) AM Peak Hour Volumes – Other Local Intersections	3-163
Figure 3.3-60	Build Alternative A (2022) PM Peak Hour Volumes – West Taunton	3-164
Figure 3.3-61	Build Alternative A (2022) PM Peak Hour Volumes – East Taunton	3-165

## List of Figures (Continued)

---

Figure 3.3-62	Build Alternative A (2022) PM Peak Hour Volumes – Route 44 Corridor	3-166
Figure 3.3-63	Build Alternative A (2022) PM Peak Hour Volumes – Other Local Intersections	3-167
Figure 3.3-64	Build Alternative A (2022) Saturday Midday Peak Hour Volumes – West Taunton	3-168
Figure 3.3-65	Build Alternative A (2022) Saturday Midday Peak Hour Volumes – East Taunton	3-169
Figure 3.3-66	Build Alternative A (2022) Saturday Midday Peak Hour Volumes – Route 44 Corridor	3-170
Figure 3.3-67	Build Alternative A (2022) Saturday Midday Peak Hour Volumes – Other Local Intersections	3-171
Figure 3.3-68	Build Alternative A (2022) Interchange Volumes – Route 140 Interchanges	3-172
Figure 3.3-69	Build Alternative A (2022) Interchange Volumes – Route 24 Interchanges	3-173
Figure 3.3-70	Build Alternative A (2022) Interchange Volumes – Other Area Interchanges	3-174
Figure 3.3-71	Build Alternative A (2022) Intersection LOS Summary – West Taunton	3-175
Figure 3.3-72	Build Alternative A (2022) Intersection LOS Summary – East Taunton	3-176
Figure 3.3-73	Build Alternative A (2022) Intersection LOS Summary – Route 44 Corridor	3-177
Figure 3.3-74	Build Alternative A (2022) Intersection LOS Summary – Other Local Intersections	3-178
Figure 3.3-75	Build Alternative A (2022) Interchange LOS Summary – Route 140 Interchanges	3-181
Figure 3.3-76	Build Alternative A (2022) Interchange LOS Summary – Route 24 Interchanges	3-182
Figure 3.3-77	Build Alternative A (2022) Interchange LOS Summary – Other Area Interchanges	3-183
Figure 3.3-78	Proposed Improvements: Galleria Mall Drive South/Overpass Connector/Route 140 Southbound and Northbound Ramps	3-187
Figure 3.3-79	Proposed Improvements: Stevens Street Signal Improvements	3-188
Figure 3.3-80	Proposed Improvements: Site Driveways	3-189
Figure 3.3-81	Proposed Improvements: Route 24 Northbound and Southbound Ramps/Route 140	3-191
Figure 3.3-82	Proposed Improvements: Route 24 Northbound and Southbound Ramps/Route 140 at Intersections	3-193
Figure 3.3-83	Proposed Cross-Section: Route 140 under Route 24 Bridge	3-194
Figure 3.3-84	Build Alternative A Mitigated (2022) Interchange	3-195
Figure 3.3-85	Build Alternative A Mitigated (2022) AM Peak Hour Volumes	3-196
Figure 3.3-86	Build Alternative A Mitigated (2022) PM Peak Hour Volumes	3-197
Figure 3.3-87	Build Alternative A Mitigated (2022) Saturday Midday Peak Hour Volumes	3-198
Figure 3.3-88	Build Alternative A Mitigated (2022) Intersection LOS Summary – West Taunton	3-205



## List of Figures (Continued)

---

Figure 3.3-89	Build Alternative A Mitigated (2022) Intersection LOS Summary – East Taunton	3-206
Figure 3.3-90	Build Alternative A Mitigated (2022) Intersection LOS Summary – Route 44 Corridor	3-207
Figure 3.3-91	Build Alternative A Mitigated (2022) Intersection LOS Summary – Other Local Intersections	3-208
Figure 3.3-92	Build Alternative A Mitigated (2022) Interchange LOS Summary	3-210
Figure 3.3-93	Site Circulation: Alternative B	3-211
Figure 3.3-94	Build Alternative B (2022) AM Peak Hour Volumes	3-213
Figure 3.3-95	Build Alternative B (2022) PM Peak Hour Volumes	3-214
Figure 3.3-96	Build Alternative B (2022) Saturday Midday Peak Hour Volumes	3-215
Figure 3.3-97	Build Alternative B (2022) Intersection LOS Summary	3-216
Figure 3.3-98	Proposed Improvements: Stevens Street	3-219
Figure 3.3-99	Build Alternative B Mitigated (2022) Intersection LOS Summary	3-220
Figure 3.3-100	Proposed Public Transportation Services	3-224
Figure 3.3-101	Proposed Casino Shuttle Services	3-225
Figure 3.4-1	No-Build (2032) Interchange Volumes – Route 140 Interchanges	3-230
Figure 3.4-2	No-Build (2032) Interchange LOS Summary – Route 140 Interchanges	3-231
Figure 3.4-3	Build Alternative A (2032) Interchange Volumes – Route 140 Interchanges	3-232
Figure 3.4-4	Build Alternative A (2032) Interchange LOS Summary – Route 140 Interchanges	3-233
Figure 3.4-5	No-Build (2032) Interchange Volumes – Route 140 Interchanges with MassDOT Option 1D	3-235
Figure 3.4-6	No-Build (2032) Interchange LOS Summary – Route 140 Interchanges with MassDOT Option 1D	3-236
Figure 3.4-7	Build Alternative A (2032) Interchange Volumes – Route 140 Interchanges with MassDOT Option 1D	3-238
Figure 3.4-8	Build Alternative A (2032) Interchange LOS Summary – Route 140 Interchanges with MassDOT Option 1D	3-239
Figure 5.8-1	FAA Height Restrictions Map	5-25
Figure 5.8-2	Typical Solar Hot Water System	5-27
Figure 5.8-3	Energy to the Solar Hot Water System	5-29
Figure 5.8-4	Energy Use of the Solar Hot Water System	5-30
Figure 5.8-5	Shadows at 9:00 AM on December 21	5-33
Figure 5.8-6	Shadows at 3:00 PM on December 21	5-34
Figure 5.8-7	Perspective View of Podium and Hotel Tower Modules	5-35
Figure 5.8-8	Areas Suitable for Canopy Systems Over Surface Parking Areas	5-36
Figure 5.9-1	Wind Energy Resources in Massachusetts	5-42

## List of Figures (Continued)

---

Figure 6.1-1	Assawompset Pond Complex	6-12
Figure 6.1-2	Existing Water Distribution System	6-13
Figure 6.3-1	Alternative A – Proposed Project Water System Improvements	6-14
Figure 6.3-2	Alternative B – Reduced Intensity I Water System Improvements	6-15
Figure 6.3-3	Alternative C – Reduced Intensity II Water System Improvements	6-16
Figure 7.2-1	Wastewater System with Proposed Improvements	7-9
Figure 8.1-1	Ground Cover – Existing Conditions	8-4
Figure 8.2-1	Ground Cover – Proposed Conditions (Alternative A)	8-5
Figure 8.2-2	Ground Cover – Alternative B	8-6
Figure 8.2-3	Ground Cover – Alternative C	8-7
Figure 8.2-4	Ground Cover – No Action Conditions (Alternative D)	8-8
Figure 9.2-1	USGS Locus Map	9-4
Figure 9.2-2	Wetland Resource Areas	9-5
Figure 9.5-1	Wetland Resource Area Impacts - Preferred Alternative Project Site (South)	9-12
Figure 9.5-2	Wetland Resource Area Impacts - Preferred Alternative Project Site (North)	9-13
Figure 9.5-3	Wetland Resource Area Impacts - Alternative B Project Site (South)	9-18
Figure 9.5-4	Wetland Resource Area Impacts - Alternative B Project Site (North)	9-19
Figure 9.5-5	Wetland Resource Area Impacts - Alternative C Project Site (South)	9-20
Figure 9.5-6	Wetland Resource Area Impacts - No Action Alternative (South)	9-21
Figure 9.5-7	Wetland Resource Area Impacts - No Action Alternative (North)	9-22
Figure 9.6-1	Off-site Improvements – Traffic Mitigation Options for Northwest Quadrant	9-26
Figure 9.6-2	Off-site Improvements – Traffic Mitigation Options for Southwest Quadrant	9-27
Figure 9.6-3	Off-site Improvements – Traffic Mitigation Options for Northeast Quadrant	9-28
Figure 9.6-4	Off-site Improvements – Traffic Mitigation, 1.5:1 Slope (Preferred)	9-35
Figure 9.6-5	Off-site Improvements – Traffic Mitigation, 2:1 Slope	9-36
Figure 9.6-6	Off-site Improvements – Traffic Mitigation, Retaining Wall	9-37
Figure 9.7-1	Potential Candidate Sites for Wetland Replication/Compensatory Flood Storage Areas	9-42
Figure 10.1-1	Existing Stormwater Management System on Project Site	10-2
Figure 10.1-2	Existing Stormwater Management System at Route 24/140 Interchange	10-3
Figure 10.2-1	Conceptual Stormwater Management System Plan (South Parcels)	10-9
Figure 10.2-2	Conceptual Stormwater Management System Plan (North Parcels)	10-10
Figure 10.2-3	Proposed Off-Site Stormwater Management System	10-15
Figure 13.3-1	Construction Truck Traffic	13-15

## List of Tables

---

Table 1.7-1	Consultation Meetings	1-13
Table 1.8-1	Anticipated Permits and Approvals	1-18
Table 1.11-1	Changes in Environmental Impacts	1-20
Table 2.2-1	Summary of Development Alternatives	2-3
Table 2.2-2	No Action Alternative Parcels	2-5
Table 3.2-1	Average Daily Traffic Summary	3-30
Table 3.2-2	Original Study Area Crash Rate Summary	3-50
Table 3.2-3	Expanded 2012 Area Crash Rate Summary	3-51
Table 3.2-4	Route 24 and 140 Freeway Segment Crash Summary	3-52
Table 3.2-5	Level of Service Criteria (HCM Excerpt)	3-55
Table 3.2-6	LOS Criteria for Merge and Diverge Segments (HCM Excerpt)	3-56
Table 3.2-7	LOC Criteria for Weaving Segments (HCM Excerpt)	3-57
Table 3.2-8	LOS Criteria for Basic Freeway Segments (HCM Excerpt)	3-57
Table 3.3-1	Liberty & Union Industrial Park: Phase 2 Estimated Trip Generation at Approved Full Build-Out	3-92
Table 3.3-2	Liberty & Union Industrial Park: Phase 1 Estimated Additional Trip Generation at Approved Full Build-Out	3-93
Table 3.3-3	Hourly Casino/Hotel Volumes Based on Gaming Positions: Weekday	3-125
Table 3.3-4	Hourly Casino/Hotel Volumes Based on Gaming Positions: Saturday	3-125
Table 3.3-5	Trip Generation Summary: Preferred Alternative	3-128
Table 3.3-6	Summary of Mitigation Measures: Alternative A	3-202
Table 3.3-7	MassDOT Alternative 1D Responsibility Matrix	3-203
Table 3.3-8	Summary of Parking Demand and Supply by Alternative	3-221
Table 4.2-1	National Ambient Air Quality Standards	4-1
Table 4.2-2	Observed Ambient Air Quality Concentrations	4-3
Table 4.4-1	Regional Mesoscale (Indirect) Emissions Analysis Summary (No Action)	4-5
Table 4.4-2	Regional Mesoscale (Indirect) Emissions Analysis Summary (Alternative A)	4-5
Table 4.4-3	Regional Mesoscale (Indirect) Emissions Analysis Summary (Alternative B)	4-5
Table 4.4-4	Regional Mesoscale (Indirect) Emissions Analysis Summary (Alternative A with Mitigation)	4-6
Table 4.4-5	Regional Mesoscale (Indirect) Emissions Analysis Summary (Alternative B with Mitigation)	4-6
Table 5.3-1	Transportation Greenhouse Gas Emissions	5-7
Table 5.5-1	Water Park Greenhouse Gas Emissions	5-8
Table 5.6-1	Estimates of Preferred Alternative Direct GHG Emissions	5-9
Table 5.6-2	Estimates of Preferred Alternative Indirect GHG Emissions	5-10

## List of Tables (Continued)

---

Table 5.6-3	Estimates of Preferred Alternative Indirect GHG Emissions	5-10
Table 5.6-4	Summary of GHG Baseline Case and GHG Mitigated Case emissions, short tons CO <sub>2</sub> /year	5-11
Table 5.8-1	Overview of Solar Thermal Energy	5-28
Table 5.8-2	Solar PV Design Parameters for Casino Podium and Hotel Tower	5-37
Table 5.8-3	Solar PV Design Parameters for Parking Lot Canopies	5-38
Table 6.1-1	Average Day Raw Water Withdrawals by Community	6-1
Table 6.1-2	Maximum Day Demands – City of New Bedford	6-2
Table 6.1-3	Maximum Day Demands versus Available WTP Capacity – City of Taunton	6-2
Table 6.1-4	DCR Service Population and Demand Projections for City of Taunton	6-3
Table 6.1-5	Current Water Uses within Project Site	6-4
Table 6.2-1	Average Day Demand Water Uses By Alternative*	6-7
Table 6.2-2	No Action Alternative Water Uses	6-10
Table 7.2-1	Wastewater Projections	7-4
Table 8.2-1	Ground Cover Changes under the Preferred Alternative	8-2
Table 8.2-2	Ground Cover Changes under Alternative B	8-2
Table 8.2-3	Ground Cover Changes under Alternative C	8-3
Table 8.2-4	Ground Cover Changes under No Action	8-9
Table 8.2-5	Summary of Parking Demand and Supply by Alternative	8-10
Table 9.2-1	Summary Descriptions of Delineated Local and State Wetland Resource Areas on the Project Site and in the Vicinity of Route 24/140 Interchange	9-6
Table 9.5-1	Alternative A: Preferred Alternative - Summary of Wetland Resource Area Impacts Regulated Under the WPA and Ordinance	9-14
Table 9.5-2	Comparison of Wetland Resource Area Alterations for the Preferred Alternative (Alternative A) and Alternative Developments	9-23
Table 9.6-1	Preferred Traffic Mitigation Alternative and Intermediate Options and their Impacts to Wetland Resource Areas	9-29
Table 10.2-1	Structural Stormwater BMPs for the Project Site	10-6
Table 10.2-2	Stormwater Management System Treatment Capacities (Preferred Alternative)	10-8
Table 10.2-3	Pre-Development Hydrologic Analysis Summary	10-11
Table 10.2-4	Post-Development Hydrologic Analysis Summary (Preferred Alternative)	10-11
Table 14.2-1	State Agency Actions	14-15

## APPENDICES

---

### Appendix A: Transportation

- A-1 Traffic Counts
- A-2 Crash Data and Worksheets
- A-3 Synchro Tables and Reports
- A-4 Highway Capacity Manual Analyses
- A-5 MassDOT Correspondence and Meeting Minutes
- A-6 Trip Generation and Trip Distribution
- A-7 Traffic Signal Warrant Analysis
- A-8 SRPEDD Trip Distribution
- A-9 Route 24/140 Interchange Plans

### Appendix B: Air Quality

- B-1 Mesoscale Analysis Calculations (including Greenhouse Gases)
- B-2 Microscale Intersection Selection Rankings
- B-3 MOBILE6.2 Microscale Emission Factor Summary
- B-4 MOBILE 6 Output Files
- B-5 CAL3QHC Output Files
- B-6 Construction Emissions
- B-7 Communications

### Appendix C: Greenhouse Gas

- C-1 Greenhouse Gas Calculations
- C-2 Visual DOE Model Output
- C-3 CHP Performance Estimate
- C-4 PVWatts Calculator
- C-5 Solar PV Financial Analysis

### Appendix D: Water Supply

- D-1 CDM Smith Letter
- D-2 BETA Group, Inc. Letter

### Appendix E: Wetlands

- E-1 Wetland Delineation Report for LIT
- E-2 Wetland Delineation Report for Off-site Resources
- E-3 Wildlife Habitat Evaluation

### Appendix F: Stormwater Report

- F-1 On-Site Stormwater Management Plan
- F-2 Off-Site Mitigation

### Appendix G: Construction

- Draft Construction Mitigation Plan